



Town of Warren
Request for Proposals

PINE HILL ROAD CULVERT REPLACEMENT

SCOPE OF WORK: PINE HILL ROAD CULVERT REPLACEMENT (Contractor)

The Town of Warren seeks a contractor to assist the Road Agent with the removal and complete installation of 10 culverts on Pine Hill Road. The contractor will be expected to provide a 12–18 ton excavator and operator to work under the direction of the Town’s Road Agent. All materials, signage, and traffic control will be supplied by the Town of Warren.

Culvert replacement will start no sooner than August 26th and be completed no later than October 31th.

ADDITIONAL REQUIREMENTS: The Contractor agrees that it will carry any and all insurance which will protect it, the Town of Warren and their officials, agents, volunteers and employees from any and all claims and demands, costs, damages, loss of service or consortium, expenses, compensation, and attorneys’ fees including but not limited to any and all claims for personal injury and/or death, workers’ compensation injuries, and property damages which may, in any way, arise from or out of the operations of the Contractor whether such operations be performed by the Contractor itself, anyone directly or indirectly employed by it or any other persons or company retained in any way to carry on all or portion of the operations, activities or work required by or related to the Contract. The Contractor further agrees that the Town of Warren and its officials, agents, volunteers and employees shall be named as an additional insured in any and all such liability insurance policies required by the Town of Warren.

BID DELIVERY: Quotes must include an hourly rate for the machine and operator and must be delivered by **August 25, 2021 at 4:00 p.m.** to

Town of Warren
PO Box 40
Warren NH 03279

or emailed to Administrator@Warren-NH.com



PINE HILL ROAD CULVERT DESCRIPTIONS AND REPLACEMENT SPECS:

Culvert #	Existing Size	Replacement Size	Location (')	Replace?
1	15	N/A	669	No
2	15	15	1834	No*
3	12	15	2769	Yes
4	15	15	3150	Yes
5	15	15	3404	Yes
6	15	15	3629	Yes
7	18	24	3983	Yes
8	15	15	4966	No*
9	15	15	5240	No*
10	15	15	5496	Yes
11	15	15	5694	Yes
12	15	15	6219	Yes
13	12	15	6426	Yes
14	15	15	6639	Yes

*** Culverts not to be replaced until later date**